BRUHAT BANAGLORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

BBMP/2021-22/OW/WORK_INDENT50952

Name of Work:Providing infrastructure Programmes to SC/ST Communities in Dasarahalli Zone

Job Code: 014-22-000005

Sl	Description of Work	Unit	Qty	Approved rates Sri.D.ANAND NAIDU (DONADI ANANAD NAIDU)	
				In figures (Rs)	In Words (Rs)
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification	Cum	1001.88	234.17	Rupees Two hundred thirty Four & Seventeen paise Only
2	Providing and laying in position plain cement concrete of mix1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	150.28	5381.62	Rupees Five thousand three hundred eighty one & Sixty two Paise Only
3	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications.	Sqm	1092.96	377.62	RupeeThree hundred Seventy seven & Sixty two paise Only

Scanned with OKEN Scanner

4	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6	Cum	364.32	6214.92	Rupees Six thousand two hundred fourteen & Ninety two paise Only
5	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (TMT bars FC 500)(P.18/4.46.2) Issue rate date : 02.11.2021 till now	Tonnes	21.86	74855.36	Rupess Seventy four thousand eight hundred fifty five & thirty six Paise only
6	Providing and and fixing Precast Concrete slab 10 CM thick witth all lead and lift as per specification (Data Rate Approved) 2018-19	Sqm	819.72	2325.55	RupessTwo thousand three hundred twenty five & fifty five Paise only
7	Transportation & disposing off the excavated earth obtained from side drains and high burns an either side of the road 2 km lead	Cum	1001.88	85.23	Rupees Eighty five & twenty three Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned with OKEN Scanner